






	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14
A 															

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14
A	E-02 DRAWING INDEX REV E 2/26														
	E-01 Cover and controlled revision status E-14 Conveyor G120C power and PROFINET control														
B	E-02 Drawing index E-15 Pump G120C power and PROFINET control														
	E-03 Design basis, legend and reference designations E-16 Motor cables, PE and shield termination														
	E-04 Single-line incoming power distribution E-17 PROFINET and OT network architecture														
C	E-05 Main distribution and branch protection E-18 HMI and NVIDIA inspection interface														
	E-06 24 VDC PELV distribution E-19 Solenoid valves and interposing relays														
	E-07 S7-1500 rack and module allocation E-20 Field sensors, flow and level instrumentation														
D	E-08 PLC digital inputs I0.0-I1.7 E-21 Stack light, local stations and capper interface														
	E-09 PLC digital inputs I2.0-I3.7 and spares E-22 Terminal strips X100 and X101														
	E-10 PLC digital outputs Q0.0-Q1.7 E-23 Terminal strips X102/X103, power, common and shields														
E	E-11 PLC digital outputs Q2.0-Q3.7 and spares E-24 Cable schedule and external field connections														
	E-12 Analog inputs and shield termination E-25 Conceptual safety interface and boundaries														
	E-13 TM Count high-speed pulse inputs E-26 Spare capacity, BOM coverage and open inputs														
F	FICTIONAL ENGINEERING PROJECT - NOT FOR CONSTRUCTION CONCEPTUAL SAFETY ARCHITECTURE - REQUIRES PROJECT-SPECIFIC RISK ASSESSMENT, DESIGN, VERIFICATION AND VALIDATION BY A QUALIFIED MACHINERY-SAFETY ENGINEER. NO PERFORMANCE LEVEL, SIL, CATEGORY, CE CONFORMITY OR REGULATORY COMPLIANCE IS CLAIMED.														
Author: FC01 engineering team				Drawing index									File: FC01_revision_e.get		
Date:													Folio: 2/26		

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14
A	E-03 DESIGN BASIS, LEGEND AND REFERENCE DESIGNATIONS														REV E 3/26
B	PROTECTIVE DEVICE =FC01+CP01-QS100 Main isolation	PLC / MODULE =FC01+CP01-A100 PLC/controller	SENSOR / INSTRUMENT =FC01+FLD-FT100 Field instrument	ACTUATOR / RELAY =FC01+FLD-YV100 Solenoid actuator	TERMINAL / SHIELD =FC01+CP01-X100..-X199 Terminal family										
C															
D															
E	Designation form: =FC01+<location>-<tag>; CP01 control panel, FD01 field, OP01 operator and IF01 external capper interface. Ordinary PNP 24 VDC field sensing; 4-20 mA analog; TM Count pulse channels; PROFINET Standard Telegram 1 for drives. PROVISIONAL: 400/230 VAC 3P+N+PE 50 Hz TN-S and 24 VDC PELV are design assumptions pending site confirmation.														
F	FICTIONAL ENGINEERING PROJECT - NOT FOR CONSTRUCTION CONCEPTUAL SAFETY ARCHITECTURE - REQUIRES PROJECT-SPECIFIC RISK ASSESSMENT, DESIGN, VERIFICATION AND VALIDATION BY A QUALIFIED MACHINERY-SAFETY ENGINEER. NO PERFORMANCE LEVEL, SIL, CATEGORY, CE CONFORMITY OR REGULATORY COMPLIANCE IS CLAIMED.														
Author: FC01 engineering team				Design basis, legend and reference designations									File: FC01_revision_e.get		
Date:													Folio: 3/26		

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14
A	E-04 SINGLE-LINE INCOMING POWER DISTRIBUTION												REV E 4/26		
B															
	=FC01+FLD-GL100 Site cable entry 3P+N+PE assumption	=FC01+CP01-QS100 Door-coupled main isolator	=FC01+CP01-QF100 Main protective device	=FC01+CP01-PE100 PE bar and enclosure bonding	=FC01+CP01-X0 Incoming distribution terminals										
C															
D															
E	Functional single-line path only; conductor sizing and protection ratings remain open and are not construction values. PE is not switched. Bond enclosure, mounting plate, door and equipment PE to PE100 using verified conductors. OPEN: supply earthing system, prospective fault current, SCCR, selectivity, voltage drop and installation method.														
F	FICTIONAL ENGINEERING PROJECT - NOT FOR CONSTRUCTION CONCEPTUAL SAFETY ARCHITECTURE - REQUIRES PROJECT-SPECIFIC RISK ASSESSMENT, DESIGN, VERIFICATION AND VALIDATION BY A QUALIFIED MACHINERY-SAFETY ENGINEER. NO PERFORMANCE LEVEL, SIL, CATEGORY, CE CONFORMITY OR REGULATORY COMPLIANCE IS CLAIMED.														
Author: FC01 engineering team				Single-line incoming power distribution								File: FC01_revision_e.get			
Date:												Folio: 4/26			

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14
A	E-05 MAIN DISTRIBUTION AND BRANCH PROTECTION														REV E 5/26
B	PROTECTIVE DEVICE =FC01+CP01-QF100 Main protective device	VARIABLE-FREQUENCY DRIVE =FC01+CP01-U100 Conveyor G120C PN	VARIABLE-FREQUENCY DRIVE =FC01+CP01-U101 Pump G120C PN	POWER SUPPLY =FC01+CP01-PS100 24 VDC 20 A supply	PROTECTIVE DEVICE =FC01+CP01-QF110 24 VDC branch protection										
C															
D															
E	Separate mains/drive routes from 24 VDC control, instrumentation and Ethernet wiring. Drive input protection, EMC accessories, braking duty and motor cable selections are provisional pending nameplates and vendor coordination.														
F	FICTIONAL ENGINEERING PROJECT - NOT FOR CONSTRUCTION CONCEPTUAL SAFETY ARCHITECTURE - REQUIRES PROJECT-SPECIFIC RISK ASSESSMENT, DESIGN, VERIFICATION AND VALIDATION BY A QUALIFIED MACHINERY SAFETY ENGINEER. NO PERFORMANCE LEVEL, SIL, CATEGORY, CE CONFORMITY OR REGULATORY COMPLIANCE IS CLAIMED.														
Author: FC01 engineering team				Main distribution and branch protection									File: FC01_revision_e.get		
Date:													Folio: 5/26		

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14
A	E-06 24 VDC PELV DISTRIBUTION REV E 6/26														
B	POWER SUPPLY =FC01+CP01-PS100 24 VDC 20 A supply	PROTECTIVE DEVICE =FC01+CP01-QF110 Electronic branch protection	PLC / MODULE =FC01+CP01-A100 PLC and local modules	NETWORK NODE =FC01+CP01-SW100 Managed switch	NETWORK NODE =FC01+CP01-PC200 NVIDIA edge compute										
C															
D															
E	Protected branches: PLC/I-O, HMI, relays/solenoids, network/security and vision/lighting; exact channel ratings remain a native design input. 0 V reference and functional-earth/shield paths are controlled separately; do not substitute shield drain for protective earth.														
F	FICTIONAL ENGINEERING PROJECT - NOT FOR CONSTRUCTION CONCEPTUAL SAFETY ARCHITECTURE - REQUIRES PROJECT-SPECIFIC RISK ASSESSMENT, DESIGN, VERIFICATION AND VALIDATION BY A QUALIFIED MACHINERY SAFETY ENGINEER. NO PERFORMANCE LEVEL, SIL, CATEGORY, CE CONFORMITY OR REGULATORY COMPLIANCE IS CLAIMED.														
Author: FC01 engineering team			24 VDC PELV distribution									File: FC01_revision_e.get			
Date:												Folio: 6/26			

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14
A	E-07 S7-1500 RACK AND MODULE ALLOCATION														REV E 7/26
B	PLC /MODULE =FC01+CP01-A100 SIMATIC S7-1500 CPU 1511-1 PN 6ES7511-1AL03-0AB0		PLC /MODULE =FC01+CP01-A101 TM Count 2x24V 6ES7550-1AA01-0AB0		PLC /MODULE =FC01+CP01-A102 DI 32x24V DC HF 6ES7521-1BL00-0AB0		PLC /MODULE =FC01+CP01-A103 DQ 32x24V DC/0.5A HF 6ES7522-1BL01-0AB0		PLC /MODULE =FC01+CP01-A104 AI 8xU/I HF 6ES7531-7NF00-0AB0						
C															
D															
E	Rack order: CPU, TM Count, DI, DQ, AI. Memory card, rail, front connectors and load-group wiring require native TIA confirmation. CPU baseline FS03/FW4.0 is a controlled assumption; delivered hardware state and exact V20 catalog compatibility remain open.														
F	FICTIONAL ENGINEERING PROJECT - NOT FOR CONSTRUCTION CONCEPTUAL SAFETY ARCHITECTURE - REQUIRES PROJECT-SPECIFIC RISK ASSESSMENT, DESIGN, VERIFICATION AND VALIDATION BY A QUALIFIED MACHINERY-SAFETY ENGINEER. NO PERFORMANCE LEVEL, SIL, CATEGORY, CE CONFORMITY OR REGULATORY COMPLIANCE IS CLAIMED.														
Author: FC01 engineering team				S7-1500 rack and module allocation									File: FC01_revision_e.get		
Date:													Folio: 7/26		

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14
A	E-08 PLC DIGITAL INPUTS I0.0-I1.7 REV E 8/26														
	I0.0 - A102/CH0 SAFETY_OK - K100 SPARE/NO FIELD TERM -/-														
B	I0.1 - A102/CH1 GUARD_CLOSED_STATUS - S102 X100:1 C001/I														
	I0.2 - A102/CH2 AIR_PRESSURE_OK - B100 X100:3 C002/I														
	I0.3 - A102/CH3 PRODUCT_SUPPLY_OK - B101 X100:6 C003/I														
	I0.4 - A102/CH4 DI_SPARE_DRIVE_REMOVED_01 SPARE SPARE/NO FIELD TERM -/-														
C	I0.5 - A102/CH5 DI_SPARE_DRIVE_REMOVED_02 SPARE SPARE/NO FIELD TERM -/-														
	I0.6 - A102/CH6 DI_SPARE_DRIVE_REMOVED_03 SPARE SPARE/NO FIELD TERM -/-														
	I0.7 - A102/CH7 DI_SPARE_DRIVE_REMOVED_04 SPARE SPARE/NO FIELD TERM -/-														
	I1.0 - A102/CH8 DI_SPARE_DRIVE_REMOVED_05 SPARE SPARE/NO FIELD TERM -/-														
	I1.1 - A102/CH9 DI_SPARE_DRIVE_REMOVED_06 SPARE SPARE/NO FIELD TERM -/-														
D	I1.2 - A102/CH10 BOTTLE_AT_NEST_1 - B110 X100:9 C004/I														
	I1.3 - A102/CH11 BOTTLE_AT_NEST_2 - B111 X100:12 C005/I														
	I1.4 - A102/CH12 GATE_OPEN_FB - B120 X100:15 C006/I														
E	I1.5 - A102/CH13 GATE_CLOSED_FB - B121 X100:18 C007/I														
	I1.6 - A102/CH14 CLAMP_RELEASED_FB - B122 X100:21 C008/I														
	I1.7 - A102/CH15 CLAMP_ENGAGED_FB - B123 X100:24 C009/I														
F	FICTIONAL ENGINEERING PROJECT - NOT FOR CONSTRUCTION CONCEPTUAL SAFETY ARCHITECTURE - REQUIRES PROJECT-SPECIFIC RISK ASSESSMENT, DESIGN, VERIFICATION AND VALIDATION BY A QUALIFIED MACHINERY-SAFETY ENGINEER. NO PERFORMANCE LEVEL, SIL, CATEGORY, CE CONFORMITY OR REGULATORY COMPLIANCE IS CLAIMED.														
Author: FC01 engineering team				PLC digital inputs I0.0-I1.7									File: FC01_revision_e.get		
Date:													Folio: 8/26		

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	
A	E-09 PLC DIGITAL INPUTS I2.0-I3.7 AND SPARES															REV E 9/26
	I2.0 -A102/CH16 FILL_VALVE_1_CLOSED_FB-B130 X101:3 C010/1															
B	I2.1 -A102/CH17 FILL_VALVE_2_CLOSED_FB-B131 X101:6 C011/1															
	I2.2 -A102/CH18 CAPPER_READY-IF140 X101:9 C012/1															
	I2.3 -A102/CH19 CAPPER_BUSY-IF140 X101:12 C012/4															
	I2.4 -A102/CH20 CAPPER_COMPLETE-IF140 X101:13 C012/5															
	I2.5 -A102/CH21 CAPPER_FAULT-IF140 X101:14 C012/6															
C	I2.6 -A102/CH22 LOCAL_RESET_PB-S100 X101:15 C013/1															
	I2.7 -A102/CH23 LOCAL_STOP_PB-S101 X101:18 C014/1															
	I3.0 -A102/CH24 DI_SPARE_01 SPARE SPARE/NO FIELD TERM -/-															
D	I3.1 -A102/CH25 DI_SPARE_02 SPARE SPARE/NO FIELD TERM -/-															
	I3.2 -A102/CH26 DI_SPARE_03 SPARE SPARE/NO FIELD TERM -/-															
	I3.3 -A102/CH27 DI_SPARE_04 SPARE SPARE/NO FIELD TERM -/-															
	I3.4 -A102/CH28 DI_SPARE_05 SPARE SPARE/NO FIELD TERM -/-															
E	I3.5 -A102/CH29 DI_SPARE_06 SPARE SPARE/NO FIELD TERM -/-															
	I3.6 -A102/CH30 DI_SPARE_07 SPARE SPARE/NO FIELD TERM -/-															
	I3.7 -A102/CH31 DI_SPARE_08 SPARE SPARE/NO FIELD TERM -/-															
F	FICTIONAL ENGINEERING PROJECT - NOT FOR CONSTRUCTION															
CONCEPTUAL SAFETY ARCHITECTURE- REQUIRES PROJECT-SPECIFIC RISK ASSESSMENT, DESIGN, VERIFICATION AND VALIDATION BY A QUALIFIED MACHINERY-SAFETY ENGINEER. NO PERFORMANCE LEVEL, SIL, CATEGORY, CE CONFORMITY OR REGULATORY COMPLIANCE IS CLAIMED.																
Author: FC01 engineering team				PLC digital inputs I2.0-I3.7 and spares									File: FC01_revision_e.get			
Date:													Folio: 9/26			

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14
A	E-10 PLC DIGITAL OUTPUTS Q0.0-Q1.7 REV E 10/26														
	Q0.0 - A103/CH0 DO_SPARE_DRIVE_REMOVED_01 SPARE SPARE/NO FIELD TERM -/- Q0.1 - A103/CH1 DO_SPARE_DRIVE_REMOVED_02 SPARE SPARE/NO FIELD TERM -/- Q0.2 - A103/CH2 FILL_VALVE_1_OPEN_CMD - K202 X101:21 C015/1 Q0.3 - A103/CH3 FILL_VALVE_2_OPEN_CMD - K203 X101:23 C016/1 Q0.4 - A103/CH4 GATE_OPEN_CMD - K204 X102:1 C017/1 Q0.5 - A103/CH5 GATE_CLOSE_CMD - K205 X102:3 C017/3 Q0.6 - A103/CH6 CLAMP_ENGAGE_CMD - K206 X102:5 C018/1 Q0.7 - A103/CH7 CLAMP_RELEASE_CMD - K207 X102:7 C018/3 Q1.0 - A103/CH8 CAPPER_REQUEST - K208 X102:9 C012/7 Q1.1 - A103/CH9 STACK_GREEN - K209 X102:11 C019/1 Q1.2 - A103/CH10 STACK_AMBER - K210 X102:13 C019/3 Q1.3 - A103/CH11 STACK_RED - K211 X102:15 C019/5 Q1.4 - A103/CH12 AUDIBLE_ALARM - K212 X102:17 C019/7 Q1.5 - A103/CH13 CAMERA_LIGHT_ENABLE - K213 X102:19 C020/1 Q1.6 - A103/CH14 DO_SPARE_01 SPARE SPARE/NO FIELD TERM -/- Q1.7 - A103/CH15 DO_SPARE_02 SPARE SPARE/NO FIELD TERM -/-														
B															
C															
D															
E															
F															
	FICTIONAL ENGINEERING PROJECT - NOT FOR CONSTRUCTION CONCEPTUAL SAFETY ARCHITECTURE - REQUIRES PROJECT-SPECIFIC RISK ASSESSMENT, DESIGN, VERIFICATION AND VALIDATION BY A QUALIFIED MACHINERY-SAFETY ENGINEER. NO PERFORMANCE LEVEL, SIL, CATEGORY, CE CONFORMITY OR REGULATORY COMPLIANCE IS CLAIMED.														
Author: FC01 engineering team				PLC digital outputs Q0.0-Q1.7									File: FC01_revision_e.get		
Date:													Folio: 10/26		

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14
A	E-11 PLC DIGITAL OUTPUTS Q2.0-Q3.7 AND SPARES REV E 11/26														
	Q2.0 - A103/CH16 DO_SPARE_03 SPARE SPARE NO FIELD TERM -/-														
B	Q2.1 - A103/CH17 DO_SPARE_04 SPARE SPARE NO FIELD TERM -/-														
	Q2.2 - A103/CH18 DO_SPARE_05 SPARE SPARE NO FIELD TERM -/-														
	Q2.3 - A103/CH19 DO_SPARE_06 SPARE SPARE NO FIELD TERM -/-														
	Q2.4 - A103/CH20 DO_SPARE_07 SPARE SPARE NO FIELD TERM -/-														
	Q2.5 - A103/CH21 DO_SPARE_08 SPARE SPARE NO FIELD TERM -/-														
C	Q2.6 - A103/CH22 DO_SPARE_09 SPARE SPARE NO FIELD TERM -/-														
	Q2.7 - A103/CH23 DO_SPARE_10 SPARE SPARE NO FIELD TERM -/-														
	Q3.0 - A103/CH24 DO_SPARE_11 SPARE SPARE NO FIELD TERM -/-														
D	Q3.1 - A103/CH25 DO_SPARE_12 SPARE SPARE NO FIELD TERM -/-														
	Q3.2 - A103/CH26 DO_SPARE_13 SPARE SPARE NO FIELD TERM -/-														
	Q3.3 - A103/CH27 DO_SPARE_14 SPARE SPARE NO FIELD TERM -/-														
	Q3.4 - A103/CH28 DO_SPARE_15 SPARE SPARE NO FIELD TERM -/-														
E	Q3.5 - A103/CH29 DO_SPARE_16 SPARE SPARE NO FIELD TERM -/-														
	Q3.6 - A103/CH30 DO_SPARE_17 SPARE SPARE NO FIELD TERM -/-														
	Q3.7 - A103/CH31 DO_SPARE_18 SPARE SPARE NO FIELD TERM -/-														
F	FICTIONAL ENGINEERING PROJECT - NOT FOR CONSTRUCTION CONCEPTUAL SAFETY ARCHITECTURE - REQUIRES PROJECT-SPECIFIC RISK ASSESSMENT, DESIGN, VERIFICATION AND VALIDATION BY A QUALIFIED MACHINERY-SAFETY ENGINEER. NO PERFORMANCE LEVEL, SIL, CATEGORY, CE CONFORMITY OR REGULATORY COMPLIANCE IS CLAIMED.														
Author: FC01 engineering team				PLC digital outputs Q2.0-Q3.7 and spares								File: FC01_revision_e.get			
Date:												Folio: 11/26			

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14
A	E-12 ANALOG INPUTS AND SHIELD TERMINATION REV E 12/26														
	IW64 -A104/CH0 FLOW_1_MA_RAW -FT100 X102:21 C021/I IW66 -A104/CH1 FLOW_2_MA_RAW -FT101 X103:1 C022/I IW68 -A104/CH2 AI_SPARE_01 SPARE SPARE/NO FIELD TERM -/- IW70 -A104/CH3 AI_SPARE_02 SPARE SPARE/NO FIELD TERM -/- IW72 -A104/CH4 AI_SPARE_03 SPARE SPARE/NO FIELD TERM -/- IW74 -A104/CH5 AI_SPARE_04 SPARE SPARE/NO FIELD TERM -/- IW76 -A104/CH6 AI_SPARE_05 SPARE SPARE/NO FIELD TERM -/- IW78 -A104/CH7 AI_SPARE_06 SPARE SPARE/NO FIELD TERM -/- FT100/FT101 are 4-20 mA channels; overall shields/drains terminate at SC100 on the panel end only unless the final EMC study requires otherwise. AI spare channels are uncommitted. Final MANA grouping, transmitter isolation and fault-range behavior require native configuration.														
B															
C															
D															
E															
F	FICTIONAL ENGINEERING PROJECT - NOT FOR CONSTRUCTION CONCEPTUAL SAFETY ARCHITECTURE - REQUIRES PROJECT-SPECIFIC RISK ASSESSMENT, DESIGN, VERIFICATION AND VALIDATION BY A QUALIFIED MACHINERY-SAFETY ENGINEER. NO PERFORMANCE LEVEL, SIL, CATEGORY, CE CONFORMITY OR REGULATORY COMPLIANCE IS CLAIMED.														
Author: FC01 engineering team				Analog inputs and shield termination									File: FC01_revision_e.get		
Date:													Folio: 12/26		

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14
A	E-13 TM COUNT HIGH-SPEED PULSE INPUTS														REV E 13/26
B	SENSOR / INSTRUMENT				PLC / MODULE				SENSOR / INSTRUMENT						
	=FC01+FLD-FT100 Flowmeter pulse channel 1 C021 core 4 to TM1.CH0.A				=FC01+CP01-A101 TM Count 2x24V CH0 A/CH1 A				=FC01+FLD-FT101 Flowmeter pulse channel 2 C022 core 4 to TM1.CH1.A						
C	TM1.CH0.A-A101/CHCH0 AFLOW_1_PULSE-FT100 X103.5 C021/4 TM1.CH1.A-A101/CHCH1 AFLOW_2_PULSE-FT101 X103.7 C022/4														
D	Pulse and 4-20 mA signals are independent diagnostics from each flowmeter; neither substitutes for the other.														
E															
F	FICTIONAL ENGINEERING PROJECT - NOT FOR CONSTRUCTION CONCEPTUAL SAFETY ARCHITECTURE - REQUIRES PROJECT-SPECIFIC RISK ASSESSMENT, DESIGN, VERIFICATION AND VALIDATION BY A QUALIFIED MACHINERY SAFETY ENGINEER. NO PERFORMANCE LEVEL, SIL, CATEGORY, CE CONFORMITY OR REGULATORY COMPLIANCE IS CLAIMED.														
Author: FC01 engineering team				TM Count high-speed pulse inputs									File: FC01_revision_e.get		
Date:													Folio: 13/26		

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14
A	E-14 CONVEYOR G120C POWER AND PROFINET CONTROL REV E 14/26														
B	PROTECTIVE DEVICE =FC01+CP01-QF100 Provisional drive branch protection VARIABLE-FREQUENCY DRIVE =FC01+CP01-U100 G120C PN conveyor drive Standard Telegram 1; IW/QW256-259 MOTOR =FC01+FLD-M100 Conveyor motor Nameplate and duty open TERMINAL / SHIELD =FC01+CP01-PE100 Motor PE/bonding														
C															
D															
E	PLC controls STW1 and speed reference; drive returns ZSW1 and actual speed. No hardwired ordinary run/ready path is claimed. External STO is conceptual safety scope and is not controlled or credited by the standard PLC.														
F	FICTIONAL ENGINEERING PROJECT - NOT FOR CONSTRUCTION CONCEPTUAL SAFETY ARCHITECTURE - REQUIRES PROJECT-SPECIFIC RISK ASSESSMENT, DESIGN, VERIFICATION AND VALIDATION BY A QUALIFIED MACHINERY-SAFETY ENGINEER. NO PERFORMANCE LEVEL, SIL, CATEGORY, CE CONFORMITY OR REGULATORY COMPLIANCE IS CLAIMED.														
Author: FC01 engineering team				Conveyor G120C power and PROFINET control									File: FC01_revision_e.get		
Date:													Folio: 14/26		

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14
A	E-16 MOTOR CABLES, PE AND SHIELD TERMINATION											REV E 16/26			
B	VARIABLE-FREQUENCY DRIVE =FC01+CP01-U100 Conveyor drive	TERMINAL / SHIELD =FC01+CP01-SC100 360-degree shield-clamp rail	MOTOR =FC01+FLD-M100 Conveyor motor	VARIABLE-FREQUENCY DRIVE =FC01+CP01-U101 Pump drive	MOTOR =FC01+FLD-M101 Pump motor										
C															
D															
E															
F															
FICTIONAL ENGINEERING PROJECT - NOT FOR CONSTRUCTION CONCEPTUAL SAFETY ARCHITECTURE - REQUIRES PROJECT-SPECIFIC RISK ASSESSMENT, DESIGN, VERIFICATION AND VALIDATION BY A QUALIFIED MACHINERY-SAFETY ENGINEER. NO PERFORMANCE LEVEL, SIL, CATEGORY, CE CONFORMITY OR REGULATORY COMPLIANCE IS CLAIMED.															
Author: FC01 engineering team				Motor cables, PE and shield termination								File: FC01_revision_e.get			
Date:												Folio: 16/26			

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14
A	E-17 PROFINET AND OT NETWORK ARCHITECTURE														REV E 17/26
B	NETWORKNODE	NETWORKNODE				PLC /MODULE			NETWORKNODE			NETWORKNODE			
	=FC01+CP01-FW100 SCALANCE S615 boundary	=FC01+CP01-SW100 SCALANCE XC208 managed switch				=FC01+CP01-A100 PLC / OPC UA server			=FC01+CP01-H100 MTP700 Unified HMI			=FC01+CP01-PC200 NVIDIA OPC UA client			
C	PLC-A100 192.168.10.10 VLAN 10 XC208 P1 CONTROL PROFINET controller /OPC UAserver HMI-H100 192.168.10.20 VLAN 10 XC208 P2 CONTROL Unified operator panel VFD-U100 192.168.10.31 VLAN 10 XC208 P3 CONTROL Conveyor G120C PN VFD-U101 192.168.10.32 VLAN 10 XC208 P4 CONTROL Pump G120C PN VISION-PC200 192.168.20.10 VLAN 20 XC208 P5 QUALITY OPC UA client+ inference ENG-SERVICE 192.168.99.0/24 VLAN 99 XC208 P6 ENGINEERING Temporary service FW-S615 Zone gateways VLAN 10/20/99 XC208 P7 trunk BOUNDARY Router/firewall														
D															
E	U100 and U101 are PROFINET nodes on the CONTROL VLAN; PC200 remains in QUALITY and never owns hazardous motion commands. Firewall rules, certificates, NTP, logging and engineering access require site cybersecurity approval.														
F	FICTIONAL ENGINEERING PROJECT - NOT FOR CONSTRUCTION CONCEPTUAL SAFETY ARCHITECTURE- REQUIRES PROJECT-SPECIFIC RISK ASSESSMENT, DESIGN, VERIFICATION AND VALIDATION BY A QUALIFIED MACHINERY-SAFETY ENGINEER. NO PERFORMANCE LEVEL, SIL, CATEGORY, CE CONFORMITY OR REGULATORY COMPLIANCE IS CLAIMED.														
Author: FC01 engineering team				PROFINET and OT network architecture									File: FC01_revision_e.get		
Date:													Folio: 17/26		

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14
A	E-18 HMI AND NVIDIA INSPECTION INTERFACE REV E 18/26														
B	NETWORKNODE =FC01+CP01-H100 MTP700 Unified Comfort PLC /MODULE =FC01+CP01-A100 Sequence and interlock authority NETWORKNODE =FC01+CP01-PC200 Non-safety quality inspection SENSOR /INSTRUMENT =FC01+FLD-CAM200 Industrial camera ACTUATOR /RELAY =FC01+FLD-LT200 Controlled vision lighting	C	D	E	F										
OPC UA transaction uses nonzero session/inspection identity, held request handshake, immutable result publication and exact acknowledgement. Missing, stale, duplicate, contradictory, uncertain, model-mismatched or timed-out AI data produces deterministic HOLD or reject disposition. NVIDIA cannot command physical outputs, drives, sequence transitions or bypass PLC interlocks.															
FICTIONAL ENGINEERING PROJECT - NOT FOR CONSTRUCTION CONCEPTUAL SAFETY ARCHITECTURE - REQUIRES PROJECT-SPECIFIC RISK ASSESSMENT, DESIGN, VERIFICATION AND VALIDATION BY A QUALIFIED MACHINERY-SAFETY ENGINEER. NO PERFORMANCE LEVEL, SIL, CATEGORY, CE CONFORMITY OR REGULATORY COMPLIANCE IS CLAIMED.															
Author: FC01 engineering team				HMI and NVIDIA inspection interface								File: FC01_revision_e.get			
Date:												Folio: 18/26			

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14
A	E-19 SOLENOID VALVES AND INTERPOSING RELAYS														REV E 19/26
	PLC / MODULE =FC01+CP01-A103 DQ 32x24V DC ACTUATOR / RELAY =FC01+CP01-K202..-K213 Interposing relay family ACTUATOR / RELAY =FC01+FLD-YV100 Gate solenoid C017 ACTUATOR / RELAY =FC01+FLD-YV101 Clamp solenoid C018 ACTUATOR / RELAY =FC01+FLD-YV102 Fill valve 1 fail closed C015														
	ACTUATOR / RELAY =FC01+FLD-YV103 Fill valve 2 fail closed C016														
	K202-K213 relay coils require D202-D213 suppression. Gate/clamp opposing commands are interlocked in PLC logic. Fill valves are fail closed; de-energized state is closed. Final coil current and protection coordination remain open.														
	FICTIONAL ENGINEERING PROJECT - NOT FOR CONSTRUCTION CONCEPTUAL SAFETY ARCHITECTURE - REQUIRES PROJECT-SPECIFIC RISK ASSESSMENT, DESIGN, VERIFICATION AND VALIDATION BY A QUALIFIED MACHINERY SAFETY ENGINEER. NO PERFORMANCE LEVEL, SIL, CATEGORY, CE CONFORMITY OR REGULATORY COMPLIANCE IS CLAIMED.														
Author: FC01 engineering team			Solenoid valves and interposing relays										File: FC01_revision_e.get		
Date:													Folio: 19/26		

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14
A	E-20 FIELD SENSORS, FLOW AND LEVEL INSTRUMENTATION														REV E 20/26
B	SENSOR / INSTRUMENT =FC01+FLD-B100 Air pressure switch	SENSOR / INSTRUMENT =FC01+FLD-B101 Product supply permissive	SENSOR / INSTRUMENT =FC01+FLD-B110 Bottle nest 1	SENSOR / INSTRUMENT =FC01+FLD-B111 Bottle nest 2	SENSOR / INSTRUMENT =FC01+FLD-FT100 Flow channel 1 pulse + 4-20 mA										
C															
D	SENSOR / INSTRUMENT =FC01+FLD-FT101 Flow channel 2 pulse + 4-20 mA	SENSOR / INSTRUMENT =FC01+FLD-B120 Gate open proof	SENSOR / INSTRUMENT =FC01+FLD-B121 Gate closed proof	SENSOR / INSTRUMENT =FC01+FLD-B122 Clamp released proof	SENSOR / INSTRUMENT =FC01+FLD-B123 Clamp engaged proof										
E	B130/B131 provide fill-valve closed proof; LT200 is vision lighting, not a process-level transmitter. All ordinary sensing is non-safety unless separately designed and validated by a qualified machinery-safety engineer.														
F	FICTIONAL ENGINEERING PROJECT - NOT FOR CONSTRUCTION CONCEPTUAL SAFETY ARCHITECTURE - REQUIRES PROJECT-SPECIFIC RISK ASSESSMENT, DESIGN, VERIFICATION AND VALIDATION BY A QUALIFIED MACHINERY-SAFETY ENGINEER. NO PERFORMANCE LEVEL, SIL, CATEGORY, CE CONFORMITY OR REGULATORY COMPLIANCE IS CLAIMED.														
Author: FC01 engineering team				Field sensors, flow and level instrumentation									File: FC01_revision_e.get		
Date:													Folio: 20/26		

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14
A	E-21 STACK LIGHT, LOCAL STATIONS AND CAPPER INTERFACE														REV E 21/26
B	DEVICE =FC01+FLD-S100 Local reset pushbutton C013		DEVICE =FC01+FLD-S101 Local controlled-stop pushbutton C014		ACTUATOR / RELAY =FC01+FLD-H101 Three-color stack light and sounder C019		TERMINAL / SHIELD =FC01+FLD-IF140 Capper ready/busy/complete/fault/request C012		PLC / MODULE =FC01+CP01-A102 DI capper/local feedback						
C															
D	PLC / MODULE =FC01+CP01-A103 DO request/indication														
E	Capper BUSY/COMPLETE is accepted only after a correlated request. Unsolicited status is a deterministic interface fault. Local stop is a controlled process stop, not an emergency-stop or protective device.														
F	FICTIONAL ENGINEERING PROJECT - NOT FOR CONSTRUCTION CONCEPTUAL SAFETY ARCHITECTURE - REQUIRES PROJECT-SPECIFIC RISK ASSESSMENT, DESIGN, VERIFICATION AND VALIDATION BY A QUALIFIED MACHINERY-SAFETY ENGINEER. NO PERFORMANCE LEVEL, SIL, CATEGORY, CE CONFORMITY OR REGULATORY COMPLIANCE IS CLAIMED.														
Author: FC01 engineering team				Stack light, local stations and capper interface									File: FC01_revision_e.get		
Date:													Folio: 21/26		

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14						
A	E-22 TERMINAL STRIPS X100 AND X101																				
	REV E 22/26																				
B	X100:1	GUARD_CLOSED_STATUS	C001/1	I0.1	24 VDC	switched	W0003	X100:17	GATE_OPEN_FB	C006/3	I1.4	0V	W0019	X101:9	CAPPER_READY	C012/1	I2.2	24 VDC	switched	W0035	
	X100:2	GUARD_CLOSED_STATUS	C001/2	I0.1	+24VDC	fused	W0004	X100:18	GATE_CLOSED_FB	C007/1	I1.5	24 VDC	switched	W0020	X101:10	CAPPER_READY	C012/2	I2.2	+24VDC	fused	W0036
	X100:3	AIR_PRESSURE_OK	C002/1	I0.2	24 VDC	switched	W0005	X100:19	GATE_CLOSED_FB	C007/2	I1.5	+24VDC	fused	W0021	X101:11	CAPPER_READY	C012/3	I2.2	0V	W0037	
	X100:4	AIR_PRESSURE_OK	C002/2	I0.2	+24VDC	fused	W0006	X100:20	GATE_CLOSED_FB	C007/3	I1.5	0V	W0022	X101:12	CAPPER_BUSY	C012/4	I2.3	24 VDC	switched	W0038	
	X100:5	AIR_PRESSURE_OK	C002/3	I0.2	0V	W0007	X100:21	CLAMP_RELEASED_FB	C008/1	I1.6	24 VDC	switched	W0023	X101:13	CAPPER_COMPLETE	C012/5	I2.4	24 VDC	switched	W0039	
	X100:6	PRODUCT_SUPPLY_OK	C003/1	I0.3	24 VDC	switched	W0008	X100:22	CLAMP_RELEASED_FB	C008/2	I1.6	+24VDC	fused	W0024	X101:14	CAPPER_FAULT	C012/6	I2.5	24 VDC	switched	W0040
	X100:7	PRODUCT_SUPPLY_OK	C003/2	I0.3	+24VDC	fused	W0009	X100:23	CLAMP_RELEASED_FB	C008/3	I1.6	0V	W0025	X101:15	LOCAL_RESET_PB	C013/1	I2.6	24 VDC	switched	W0041	
	X100:8	PRODUCT_SUPPLY_OK	C003/3	I0.3	0V	W0010	X100:24	CLAMP_ENGAGED_FB	C009/1	I1.7	24 VDC	switched	W0026	X101:16	LOCAL_RESET_PB	C013/2	I2.6	+24VDC	fused	W0042	
C	X100:9	BOTTLE_AT_NEST_1	C004/1	I1.2	24 VDC	switched	W0011	X101:1	CLAMP_ENGAGED_FB	C009/2	I1.7	+24VDC	fused	W0027	X101:17	LOCAL_RESET_PB	C013/3	I2.6	0V	W0043	
	X100:10	BOTTLE_AT_NEST_1	C004/2	I1.2	+24VDC	fused	W0012	X101:2	CLAMP_ENGAGED_FB	C009/3	I1.7	0V	W0028	X101:18	LOCAL_STOP_PB	C014/1	I2.7	24 VDC	switched	W0044	
	X100:11	BOTTLE_AT_NEST_1	C004/3	I1.2	0V	W0013	X101:3	RLL_VALVE_1_CLOSED_FB	C010/1	I2.0	24 VDC	switched	W0029	X101:19	LOCAL_STOP_PB	C014/2	I2.7	+24VDC	fused	W0045	
	X100:12	BOTTLE_AT_NEST_2	C005/1	I1.3	24 VDC	switched	W0014	X101:4	RLL_VALVE_1_CLOSED_FB	C010/2	I2.0	+24VDC	fused	W0030	X101:20	LOCAL_STOP_PB	C014/3	I2.7	0V	W0046	
D	X100:13	BOTTLE_AT_NEST_2	C005/2	I1.3	+24VDC	fused	W0015	X101:5	RLL_VALVE_1_CLOSED_FB	C010/3	I2.0	0V	W0031	X101:21	RLL_VALVE_1_OPEN_CMD	C015/1	Q0.2	+24VDC	switched	W0050	
	X100:14	BOTTLE_AT_NEST_2	C005/3	I1.3	0V	W0016	X101:6	RLL_VALVE_2_CLOSED_FB	C011/1	I2.1	24 VDC	switched	W0032	X101:22	RLL_VALVE_1_OPEN_CMD	C015/2	Q0.2	0V	W0051		
	X100:15	GATE_OPEN_FB	C006/1	I1.4	24 VDC	switched	W0017	X101:7	RLL_VALVE_2_CLOSED_FB	C011/2	I2.1	+24VDC	fused	W0033	X101:23	RLL_VALVE_2_OPEN_CMD	C016/1	Q0.3	+24VDC	switched	W0055
	X100:16	GATE_OPEN_FB	C006/2	I1.4	+24VDC	fused	W0018	X101:8	RLL_VALVE_2_CLOSED_FB	C011/3	I2.1	0V	W0034	X101:24	RLL_VALVE_2_OPEN_CMD	C016/2	Q0.3	0V	W0056		
E																					
F	FICTIONAL ENGINEERING PROJECT - NOT FOR CONSTRUCTION																				
	CONCEPTUAL SAFETY ARCHITECTURE - REQUIRES PROJECT-SPECIFIC RISK ASSESSMENT, DESIGN, VERIFICATION AND VALIDATION BY A QUALIFIED MACHINERY-SAFETY ENGINEER. NO PERFORMANCE LEVEL, SIL, CATEGORY, CE CONFORMITY OR REGULATORY COMPLIANCE IS CLAIMED.																				
Author: FC01 engineering team				Terminal strips X100 and X101											File: FC01_revision_e.get						
Date:															Folio: 22/26						

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14
A	E-23 TERMINAL STRIPS X102/X103, POWER, COMMON AND SHIELDS														REV E 23/26
B	X102:1 GATE_OPEN_CMD C017 /I Q0.4 +24VDC switched W0060					X102:13 STACK_AMBER C019 /3 Q1.2 +24VDC switched W0090					X103:1 FLOW_2_MA_RAW C022 /I IW66 4-20mA W0111				
	X102:2 GATE_OPEN_CMD C017 /2 Q0.4 0V W0061					X102:14 STACK_AMBER C019 /4 Q1.2 0V W0091					X103:2 FLOW_2_MA_RAW C022 /2 IW66 +24VDC fused W0112				
	X102:3 GATE_CLOSE_CMD C017 /3 Q0.5 +24VDC switched W0065					X102:15 STACK_RED C019 /5 Q1.3 +24VDC switched W0095					X103:3 FLOW_2_MA_RAW C022 /3 IW66 0V analog W0113				
	X102:4 GATE_CLOSE_CMD C017 /4 Q0.5 0V W0066					X102:16 STACK_RED C019 /6 Q1.3 0V W0096					X103:4 FLOW_2_MA_RAW C022 /5 IW66 FE W0114				
C	X102:5 CLAMP_ENGAGE_CMD C018 /I Q0.6 +24VDC switched W0070					X102:17 AUDIBLE_ALARM C019 /7 Q1.4 +24VDC switched W0100					X103:5 FLOW_1_PULSE C021 /4 TMLCH0.A 24 V pulse W0115				
	X102:6 CLAMP_ENGAGE_CMD C018 /2 Q0.6 0V W0071					X102:18 AUDIBLE_ALARM C019 /8 Q1.4 0V W0101					X103:6 FLOW_1_PULSE C021 /5 TMLCH0.A 0V W0116				
	X102:7 CLAMP_RELEASE_CMD C018 /3 Q0.7 +24VDC switched W0075					X102:19 CAMERA_LIGHT_ENABLE C020 /I Q1.5 +24VDC switched W0105					X103:7 FLOW_2_PULSE C022 /4 TMLCH1.A 24 V pulse W0117				
	X102:8 CLAMP_RELEASE_CMD C018 /4 Q0.7 0V W0076					X102:20 CAMERA_LIGHT_ENABLE C020 /2 Q1.5 0V W0106					X103:8 FLOW_2_PULSE C022 /5 TMLCH1.A 0V W0118				
D	X102:9 CAPPER_REQUEST C012 /7 Q1.0 +24VDC switched W0080					X102:21 FLOW_1_MA_RAW C021 /I IW64 4-20mA W0107					X24:+24V X24:+24V -/- +24VDC				
	X102:10 CAPPER_REQUEST C012 /8 Q1.0 0V W0081					X102:22 FLOW_1_MA_RAW C021 /2 IW64 +24VDC fused W0108					X0:0V X0:0V -/- 0V				
	X102:11 STACK_GREEN C019 /I Q1.1 +24VDC switched W0085					X102:23 FLOW_1_MA_RAW C021 /3 IW64 0V analog W0109					X0:MANA X0:MANA -/- 0V analog				
E	X102:12 STACK_GREEN C019 /2 Q1.1 0V W0086					X102:24 FLOW_1_MA_RAW C021 /5H IW64 FE W0110					SC100:1 SC100:1 -/- FE				
	FICTIONAL ENGINEERING PROJECT - NOT FOR CONSTRUCTION														
F	CONCEPTUAL SAFETY ARCHITECTURE - REQUIRES PROJECT-SPECIFIC RISK ASSESSMENT, DESIGN, VERIFICATION AND VALIDATION BY A QUALIFIED MACHINERY SAFETY ENGINEER. NO PERFORMANCE LEVEL, SIL, CATEGORY, CE CONFORMITY OR REGULATORY COMPLIANCE IS CLAIMED.														
Author: FC01 engineering team				Terminal strips X102/X103, power, common and shields										File: FC01_revision_e.get	
Date:														Folio: 23/26	

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14
A	E-24 CABLE SCHEDULE AND EXTERNAL FIELD CONNECTIONS														REV E 24/26
	C001 =FC01+CP01 panel terminals -> =FC01+FLD-S102 Industrial control cores 2/4 None scheduled 24 VDC control							C012 =FC01+CP01 panel terminals -> =FC01+FLD-IFJ40 Industrial control cores 8/12 None scheduled 24 VDC control							
B	C002 =FC01+CP01 panel terminals -> =FC01+FLD-B100 Industrial control cores 3/4 None scheduled 24 VDC control							C013 =FC01+CP01 panel terminals -> =FC01+FLD-S100 Industrial control cores 3/4 None scheduled 24 VDC control							
	C003 =FC01+CP01 panel terminals -> =FC01+FLD-B101 Industrial control cores 3/4 None scheduled 24 VDC control							C014 =FC01+CP01 panel terminals -> =FC01+FLD-S101 Industrial control cores 3/4 None scheduled 24 VDC control							
C	C004 =FC01+CP01 panel terminals -> =FC01+FLD-B110 Industrial control cores 3/4 None scheduled 24 VDC control							C015 =FC01+CP01 panel terminals -> =FC01+FLD-YV102 Industrial control cores 2/4 None scheduled 24 VDC control							
	C005 =FC01+CP01 panel terminals -> =FC01+FLD-B111 Industrial control cores 3/4 None scheduled 24 VDC control							C016 =FC01+CP01 panel terminals -> =FC01+FLD-YV103 Industrial control cores 2/4 None scheduled 24 VDC control							
D	C006 =FC01+CP01 panel terminals -> =FC01+FLD-B120 Industrial control cores 3/4 None scheduled 24 VDC control							C017 =FC01+CP01 panel terminals -> =FC01+FLD-YV100 Industrial control cores 4/8 None scheduled 24 VDC control							
	C007 =FC01+CP01 panel terminals -> =FC01+FLD-B121 Industrial control cores 3/4 None scheduled 24 VDC control							C018 =FC01+CP01 panel terminals -> =FC01+FLD-YV101 Industrial control cores 4/8 None scheduled 24 VDC control							
E	C008 =FC01+CP01 panel terminals -> =FC01+FLD-B122 Industrial control cores 3/4 None scheduled 24 VDC control							C019 =FC01+CP01 panel terminals -> =FC01+FLD-H101 Industrial control cores 8/12 None scheduled 24 VDC control							
	C009 =FC01+CP01 panel terminals -> =FC01+FLD-B123 Industrial control cores 3/4 None scheduled 24 VDC control							C020 =FC01+CP01 panel terminals -> =FC01+FLD-LT200 Industrial control cores 2/4 None scheduled 24 VDC control							
F	C010 =FC01+CP01 panel terminals -> =FC01+FLD-B130 Industrial control cores 3/4 None scheduled 24 VDC control							C021 =FC01+CP01 panel terminals -> =FC01+FLD-FT100 Shielded instrumentation cores 5/8 Separate overall shield/drain to SC100; not counted as an insulated core Analog/instrument							
	C011 =FC01+CP01 panel terminals -> =FC01+FLD-B131 Industrial control cores 3/4 None scheduled 24 VDC control							C022 =FC01+CP01 panel terminals -> =FC01+FLD-FT101 Shielded instrumentation cores 5/8 Separate overall shield/drain to SC100; not counted as an insulated core Analog/instrument							
Cable/core identifiers on this folio are copied from the controlled schedule; conductor sizes remain blank pending site and installation data.															
C021/C022 instrumentation shields terminate at SC100. Power and VFD motor cables remain open schedule inputs.															
FICTIONAL ENGINEERING PROJECT - NOT FOR CONSTRUCTION															
CONCEPTUAL SAFETY ARCHITECTURE - REQUIRES PROJECT-SPECIFIC RISK ASSESSMENT, DESIGN, VERIFICATION AND VALIDATION BY A QUALIFIED MACHINERY SAFETY ENGINEER. NO PERFORMANCE LEVEL, SIL, CATEGORY, CE CONFORMITY OR REGULATORY COMPLIANCE IS CLAIMED.															
Author: FC01 engineering team				Cable schedule and external field connections								File: FC01_revision_e.get			
Date:												Folio: 24/26			

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14
A	E-25 CONCEPTUAL SAFETY INTERFACE AND BOUNDARIES														REV E 25/26
	CONCEPTUAL SAFETY INTERFACE =FC01+FLD-S102 Guard-status monitoring mirror CONCEPTUAL SAFETY INTERFACE =FC01+CP01-K100 External safety-interface monitoring contact PLC / MODULE =FC01+CP01-A102 Ordinary PLC status monitoring only VARIABLE-FREQUENCY DRIVE =FC01+CP01-U100 External STO conceptual interface VARIABLE-FREQUENCY DRIVE =FC01+CP01-U101 External STO conceptual interface														
B															
C															
D															
E	CONCEPTUAL SAFETY ARCHITECTURE - REQUIRES PROJECT-SPECIFIC RISK ASSESSMENT, DESIGN, VERIFICATION AND VALIDATION BY A QUALIFIED MACHINERY-SAFETY ENGINEER. NO PERFORMANCE LEVEL, SIL, CATEGORY, CE CONFORMITY OR REGULATORY COMPLIANCE IS CLAIMED. Standard PLC, HMI and NVIDIA functions receive status only and receive no safety credit. OPEN: hazard analysis, protective-device selection, reset/restart design, PL/SIL/category determination and validation.														
F	FICTIONAL ENGINEERING PROJECT - NOT FOR CONSTRUCTION CONCEPTUAL SAFETY ARCHITECTURE - REQUIRES PROJECT-SPECIFIC RISK ASSESSMENT, DESIGN, VERIFICATION AND VALIDATION BY A QUALIFIED MACHINERY-SAFETY ENGINEER. NO PERFORMANCE LEVEL, SIL, CATEGORY, CE CONFORMITY OR REGULATORY COMPLIANCE IS CLAIMED.														
Author: FC01 engineering team				Conceptual safety interface and boundaries									File: FC01_revision_e.get		
Date:													Folio: 25/26		

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	
A	E-26 SPARE CAPACITY, BOM COVERAGE AND OPEN INPUTS														REV E 26/26	
	=FC01+CP01-A100 SIMATIC S7-1500 CPU 1511-1 PN Selected baseline					=FC01+CP01-K100 Main control enable contactor / external safety interface with dry monitoring contact TBD					=FC01+FLD-S102 Guard status dry-contact monitoring interface TBD					
B	=FC01+CP01-A101 TM Count 2x24V Selected baseline					=FC01+CP01-K202...K213 Interposing relays with bases and status indication TBD					=FC01+FLD-H101 Three-color stack light with sounder TBD					
	=FC01+CP01-A102 DI 32x24V DC HF Selected baseline					=FC01+CP01-D202...D213 Coil suppression modules TBD					=FC01+FLD-IF140 Copper interface terminals/relays TBD					
	=FC01+CP01-A103 DQ 32x24V DC/0.5A HFS Selected baseline					=FC01+CP01-X100...X199 DIN-rail terminal blocks, disconnect/test where required Provisional quantity					=FC01+FLD-CAM200 Industrial camera TBD					
	=FC01+CP01-A104 AI 8xU/I HF Selected baseline					=FC01+CP01-PE100 Copper protective-earth bar and bonding hardware TBD					=FC01+FLD-LENS200 C-mount lens TBD					
	=FC01+CP01-H100 MTP 700 Unified Comfort S elected baseline					=FC01+CP01-SC100 Shield-clamp rail and spring clamps Provisional quantity					=FC01+FLD-LT200 Machine-vision backlight/front-light assembly TBD					
C	=FC01+CP01-U100 SINAMICS G120C PN 0.75 kW unfiltered Provisional					=FC01+CP01-ENC100 IP-rated enclosure with mounting plate TBD					=FC01+FLD-CB200 Industrial Jetson carrier TBD					
	=FC01+CP01-U101 SINAMICS G120C PN 0.75 kW unfiltered Provisional					=FC01+CP01-WD100 Slotted wiring duct set TBD					=FC01+FLD-W900 Industrial Ethernet patch cables/connectors Provisional quantity					
	=FC01+CP01-SW100 SCALANCE XC208 managed Selected network baseline					=FC01+CP01-DR100 35 mm DIN rail set TBD					=FC01+FLD-W901 Shielded VFD motor cables and EMC termination kits TBD					
	=FC01+CP01-FW100 SCALANCE S615 EEC S elected network baseline					=FC01+FLD-GL100 Cable glands and EMC glands TBD					=FC01+FLD-CONS100 Markers, femules, lugs, ties and installation consumables TBD					
	=FC01+CP01-PC200 Jetson Orin NX 16GB on industrial carrier Architecture only					=FC01+CP01-FAN100 Filter fan / cooling solution TBD					=FC01+FLD-B100 Pneumatic pressure switch TBD					
D	=FC01+CP01-MC100 SIMATIC memory card; capacity to be selected after compiled project sizing TBD					=FC01+FLD-M100 Conveyor motor TBD					=FC01+FLD-B101 Product supply permissive TBD					
	=FC01+CP01-RA100 S7-1500 mounting rail and fixing hardware TBD					=FC01+FLD-M101 Pump motor TBD					=FC01+FLD-B110 Bottle 1 position sensor TBD					
	=FC01+CP01-FC100 Front connector for DI module TBD					=FC01+FLD-YV100 Gate valve/cylinder solenoid TBD					=FC01+FLD-B111 Bottle 2 position sensor TBD					
	=FC01+CP01-FC101 Front connector for DQ module TBD					=FC01+FLD-YV101 Clamp valve/cylinder solenoid TBD					=FC01+FLD-B120 Gate open feedback TBD					
	=FC01+CP01-FC102 Front connector for AI module TBD					=FC01+FLD-YV102 Fill valve channel 1, fail closed TBD					=FC01+FLD-B121 Gate closed feedback TBD					
E	=FC01+CP01-FC103 Front connector for TM Count module TBD					=FC01+FLD-YV103 Fill valve channel 2, fail closed TBD					=FC01+FLD-B122 Clamp released feedback TBD					
	=FC01+CP01-QS100 Main door-coupled isolator TBD					=FC01+FLD-FT100 Pulse plus 4-20 mA flowmeter channel 1 TBD					=FC01+FLD-B123 Clamp engaged feedback TBD					
	=FC01+CP01-QF100 Main protective device TBD					=FC01+FLD-FT101 Pulse plus 4-20 mA flowmeter channel 2 TBD					=FC01+FLD-B130 Valve 1 closed proof TBD					
	=FC01+CP01-PS100 24 VDC 20 A power supply Provisional					=FC01+FLD-S100 Local reset pushbutton TBD					=FC01+FLD-B131 Valve 2 closed proof TBD					
	=FC01+CP01-QF110 24 VDC electronic branch protection TBD					=FC01+FLD-S101 Local controlled-stop pushbutton TBD										
F	Controlled spare capacity: 8 DI, 18 DO and 6 AI allocated spares; spare terminals/cores require final allocation and labeling.															
	OPEN: supply/fault current, motor and pump data, cable routes, conductor sizing, thermal/EMC study, exact PC200 envelope and construction review.															
	FICTIONAL ENGINEERING PROJECT - NOT FOR CONSTRUCTION															
CONCEPTUAL SAFETY ARCHITECTURE - REQUIRES PROJECT-SPECIFIC RISK ASSESSMENT, DESIGN, VERIFICATION AND VALIDATION BY A QUALIFIED MACHINERY SAFETY ENGINEER. NO PERFORMANCE LEVEL, SIL, CATEGORY, CE CONFORMITY OR REGULATORY COMPLIANCE IS CLAIMED.																
Author: FC01 engineering team				Spare capacity, BOM coverage and open inputs											File: FC01_revision_e.get	
Date:															Folio: 26/26	